City of Dunn - 2017 Street Resurfacing Program
with selected Reduced Scope Summary for selected streets
Last Updated September 18, 2017

DAVIS • MARTIN • POWELL
ENGINEERS & SURVEYORS dmp

Street	Location	Initial Repair Methods	Initial Budget	Reduced Scope Repair Methods	Reduced Scope Budget	Comments
Best	Clinton to Magnolia	Mill, patch, resurface	$ 62,000	Just patch at intersections, no resurfacing	$ 46,000	Reduced scope does not include milling or resurfacing street
Brightwood	Extends from Rollingwood	Reclaim, pave	68,000			
Broad	McKay to General Lee	Mill, patch, resurface	372,000	Reduce to 2 blocks and combine with 1 block of Ellis		Reduced scope delays 3rd block repairs
Ellis	Cumberland to Granville	Mill, patch, resurface	830,000	Reduce to 1 block and combine with 2 blocks of Broad		Reduced scope delays repairs to other blocks of Ellis
Broad & Ellis				Combined 2 blocks Broad and 1 block Ellis	344,000	Combined reduced scope budget, and repair using mill, patch, resurface repair methods
Brunswick	Rowan to Currituck	Reclaim, pave	219,000			
Carlie C	Ashe to Private Drive	Reclaim, pave	135,000	Just patch most deteriorated areas and only resurface near Ashe Intersection	34,000	Significant truck traffic, reduced sope does not includ reclaim repair methods and does not include resurfacing entire street
Carr	Clinton to Wilson	Patch, resurface	55,000			
Carr	Orange to General Lee	Patch, mill, resurface	80,000			
Cascade	Crestview to end	Reclaim, pave	67,000	Just patch most deteriorated areas, no resurfacing	15,000	Reduced scope does not include any reclaim repairs and does not include resurfacing entire street
Cooper	Lakeshore to Wade	Patch, resurface	38,000			
Covington	Elm to end	Reclaim, pave	108,000			Reduced scope not provided due to extremely detriorated street condition
Duke	Fayetteville to Railroad	Patch, resurface	66,000			
Delano	Maple to good pavement	Patch, resurface	38,000			
King	Carr to Johnson	Patch, resurface	47,000			
King	Cumberland to Pearsall	Patch, mill, resurface	175,000			
Jackson	Spring Branch to Sampson	Patch, mill, resurface	340,000			Coordinate with NCDOT I 95 PROJECT
Lee	Cumberland to Edgerton	Patch, mill, resurface	156,000	Reduce to 1 block and add curb & gutter	104,000	Coordinate with Bojangles
Little	Spring Branch to Pearsall	Patch, mill, resurface	111,000			
Lucknow	Cumberland to Braod	Patch, mill, resurface	84,000			
Moon	Saturn to end	Storm pipe, reclaim, pave	60,000			
Bridge	On Johnson Street	Remove pavement, wedge, resurface	42,000	No change is scope	42,000	No reduction in scope
Steeplechase	Elm to end	Reclaim, pave	140,000			Reduced scope not provided due to extremely detriorated street condition
Washington	Elm to Godwin	Mill, patch, resurface	199,000	Reduce scope to 1 block, Duke to Godwin using mill, patch, resurtace repair methods	102,000	Reduced scope includes delaying repairs to other blocks
Wellons	Merry to Friendly	Patch, mill, resurface	66,000			
Wilson	Edgerton to Harnett	Patch, mill, resurface	119,000			
		Total Initial Conceptual Budget	3,677,000	Reduced Scope Conceptual Budget	687,000	

Note: It will be more economical to group future phased streets repairs with similar repair methods as color coded above for Reclaim or Mill related repairs